

US-54 Central Business District Viaduct

KDOT Project No. 54-87 KA-1647-02

Bridge No. 54-87-25.88 (374)

Bridge No. 54-87-25.95 (375)

Bridge No. 54-87-25.94 (376)

Bridge No. 54-87-25.86 (377)

BRIDGE REHABILITATION

City of Wichita, Sedgwick County



Presented to:

KANSAS STATE UNIVERSITY BRIDGE DESIGN WORKSHOP

Presented by:

Abdul Hamada, P.E.
Nichole Witushynsky, P.E.


October 9, 2015




Presentation Outline


- ◆ **Introduction**
- ◆ **Background**
- ◆ **Site Investigation**
- ◆ **Bridge Repair Plans & Repairs**
 - Clean Bridge & Install Bird Screens
 - Epoxy Resin Crack Repair
 - Blister Pour-backs/Anchorage Repair
 - Duct Grouting Operations
 - NDT Grout Verification
 - Test Lead Wire Installation
- ◆ **Conclusions**


Aerial View of US-54 CBD Viaduct




Aerial View of US-54 CBD Viaduct














Segmental Box Cross Section




Post-tension Duct Cross Section



Post-tension Duct Elevation



Post Tension Duct Anchorages



Unit Cell Web Pier East or West Blister Tendon Number
 e.g. **2EB - C2 - W2 - P6E - BT1**


Presentation Outline

- ◆ Introduction
- ◆ **Background**
- ◆ Site Investigation
- ◆ **Bridge Repair Plans & Repairs**
 - Clean Bridge & Install Bird Screens
 - Epoxy Resin Crack Repair
 - Blister Pour-backs/Anchorage Repair
 - Duct Grouting Operations
 - NDT Grout Verification
 - Test Lead Wire Installation
- ◆ **Conclusions**

Sunshine Skyway Bridge, FL



Sunshine Skyway Bridge, FL



Severe strand corrosion


6/14/2001

Column 133 NB NE Tendon



6/14/2001

Mid Bay Bridge, FL



Jamestown-Verrazzano Segmental Bridge, RI



Jamestown-Verrazzano Segmental Bridge, RI

Pier 13
Center Web
Vertical Tendon
3



Void in Pier With Dywidag Bar
Instead of Tendons

Span 9
Westbound
Draped Web
Tendon 21



Corrosion on Duct

Jamestown-Verrazzano Segmental Bridge, RI

Pier 14
Westbound
Vertical Tendon
8



View of Void Bottom
Corrosion on Duct and Tendons

Pier 14
Eastbound
Vertical Tendon
5



Corrosion on Both Duct and Tendon


Jamestown-Verrazzano Segmental Bridge, RI

Pier 14
Westbound
Vertical Tendon
2



Close-up of Anchor. Top of
Tendons Show some Corrosion

Pier 14
Center Web
Vertical 3



Tendon Found with Standing
Water inside

US-54 Wichita CBD Viaduct, KS



Known Project Issues (prior to investigation)

- ◆ PT Tendons used old generation of grout material and procedures
- ◆ Old generation of post-tensioning hard-ware system
- ◆ Lack of anchorage corrosion protection system
- ◆ The presence of PT blisters, deck, and web cracks
- ◆ In-span hinge

Investigation Strategy

- ◆ **Phase 1: Planning**
- ◆ **Phase 2: Walk-through inspection**
- ◆ **Phase 3: Limited site investigation**
- ◆ **Phase 4: Report of Condition assessment and recommendations**
- ◆ **Phase 5: Completion of the investigation and repair plans**
- ◆ **Phase 6: Rehabilitation**

Project Timeline Highlights

- ✦ **US – 54 CBD Preliminary Engineering for Investigation and Evaluation: NTP / project award on 8/20/2009**
- ✦ **Visual Site Inspection : October 16 to 21, 2009**
 - Final Report submitted in November 2009
- ✦ **Limited Site Investigation : Dec. 15, 2009 to March 27, 2010**
 - Final Report submitted in June 2010
- ✦ **Project Repair Plans:**
 - Final Plans submitted in June 2013
- ✦ **Bridge Rehabilitation: April 2014 to June 2014**
 - Final Report submitted in October 2014

Limited Site Investigation

Tested 10% Critical PT Elements

Tendon Type	Number Tested	Number with Voids	Percentage Voided	Total Feet Tested	Approximate Feet Voided
Longitudinal Web	32	19	59%	5,718 Feet	630 Feet
Longitudinal Top Slab	67	6	8.9%		
Hinge	6	0	0		
Diaphragm	11	3	27%		
Transverse Top Deck	4	1	25%		

Strategically selected elements were inspected

Tested ALL Accessible Critical PT Elements

- ◆ Draped Web tendons: **46%** of tendons inspected have voids
- ◆ Longitudinal Top tendons: **6%** of tendons inspected have voids
- ◆ Diaphragm Transverse Tendons: **25%** tendons inspected have voids
- ◆ Transverse Deck Tendons: **5%** tendons inspected have voids
- ◆ Hinge Tendon: **5%** of tendons inspected have voids
- ◆ Soft grout in the duct at six locations
- ◆ Water in the duct at multiple locations; some voids dry
- ◆ Low rates of corrosion at present

Repair Options

- ◆ Vacuum Grouting
- ◆ Vacuum Assist Grouting
- ◆ Pressure Grouting

Note: Due to tendon failure of Varina-Enon Bridge in Virginia after re-grouting of the tendon, there is a concern on the potential formation of corrosion cell when re-grouting of old / existing grout with new grout. “Dissimilar Grout Research” was initiated by PB/KDOT



Existing Grout

- ◆ Showed presence of portland cement based grout
- ◆ Showed negligible chloride content

Sample	pH, 1:1 by mass
Sample 1 Station 14	12.74
Sample 2 Station 87	12.54
Sample 3 Tendon T1	12.61

Sample	Acid-Soluble Chloride, % by mass of sample
Sample 1 Station 14	<0.006
Sample 2 Station 87	0.030
Sample 3 Tendon T1	<0.006





Research Approach

- ◆ Determine if using a second grout will provide improved corrosion protection for prestressing strands or result in accelerated corrosion
- ◆ Determine the possible consequences of leaving the voids unfilled

Testing Methods

- ◆ Half-cell Potential Test (probability of corrosion)
- ◆ Macro-cell Current Test
- ◆ Linear Polarization Resistance (corrosion rate)



Grouting Systems Examined

- ◆ SikaGrout 300PT (Sika Corp.)
- ◆ MasterFlow MB1205 High Performance Duct Grout

Testing Methods

- ◆ Half-cell Potential Test (probability of corrosion)
- ◆ Macro-cell Current Test
- ◆ Linear Polarization Resistance (corrosion rate)
- ◆ Electrochemical Impedance Spectroscopy (corrosion rate)
- ◆ Chemical analysis and pH of grouts

KU/FDOT Conclusions

- ✦ Leaving prestressing strands unprotected from elements has the potential to result in rapid corrosion of the exposed strands
- ✦ Significant corrosion activity developed in the presence of bleed water
- ✦ When paired with Portland cement grout, the pre-packaged anti-bleed grouts resulted in corrosion losses
- ✦ Of the anti-bleed grout materials evaluated, Masterflow 1205 appears superior

LFD Load Rating



BRIDGE NO.: 54-87-25.95 (375)

CARRIES: US 54 WESTBOUND (WB KELLOGG CBD VIADUCT)

BRIDGE COMPONENT	INVENTORY RATING LOAD FACTOR METHOD (RATING FACTOR)					OPERATING RATING LOAD FACTOR METHOD (RATING FACTOR)							
	H	TYPE 3	HS	TYPE 3S2	TYPE 3-3	H	TYPE 3	HS	TYPE 3S2	TYPE 3-3	T130	T170	HET
TRANSVERSE - MULTI CELL													
Serviceability Concrete	1.87	2.49	1.73	2.49	2.49	3.66	4.93	3.42	5.16	5.93	4.58	4.10	2.31
LFD - Flexural Strength	2.64	3.15	2.26	3.37	3.82	4.41	5.26	3.78	5.61	6.36	4.05	3.52	2.18
LONGITUDINAL													
Serviceability Concrete	1.28	1.10	0.79	0.88	0.88	2.05	1.76	1.26	1.41	1.41	1.52	1.40	0.78
LFD - Flexural Strength	2.05	1.65	1.15	1.18	1.12	3.42	2.76	1.92	1.97	1.86	1.70	1.46	0.90
LFD - Shear Strength	2.04	2.18	1.67	1.61	1.56	3.40	3.64	2.78	2.69	2.61	2.85	2.53	1.42

For Joint Locations of Transverse Top Deck and Longitudinal Box Girder, see Appendix C.

BRIDGE 375 - SUMMARY OF BRIDGE RATING

CITY (COUNTY): WICHITA (SEDGWICK)

BRIDGE NO.: 54-87-25.95 (375)

CARRIES: US 54 WESTBOUND (WB KELLOGG CBD VIADUCT)

OVER: LOCAL URBAN STREETS, ARKANSAS RIVER

RATINGS (TONS)


Load Factor Ratings for Load Posting Purposes Load Ratings in English Tons		
VEHICLE TYPE	INVENTORY	OPERATING
H	25.6	41.0
TYPE 3	27.5	44.0
HS	28.4	45.3
TYPE 3S2	31.6	50.7
TYPE 3-3	35.2	56.4
T130	--	98.8
T170	--	119.0
Heavy Equip. Transporter	--	85.7

MS18 Load Factor Ratings in Metric Tons (tonne) Provided in Compliance with the Decemeber 1995 FHWA NBIS Coding Guide			
INVENTORY		OPERATING	
Item 66	MS Equivalent	Item 64	MS Equivalent
25.7	14.3	41.0	22.8

Presentation Outline

- ◆ Introduction
- ◆ Background
- ◆ **Site Investigation**
- ◆ **Bridge Repair Plans & Repairs**
 - Clean Bridge & Install Bird Screens
 - Epoxy Resin Crack Repair
 - Blister Pour-backs/Anchorage Repair
 - Duct Grouting Operations
 - NDT Grout Verification
 - Test Lead Wire Installation
- ◆ **Conclusions**

Access (exterior)



Access (Span 3)



Access (Span 1)



Access (interior)



NDT Inspection

◆ Non-destructive Testing

- Void detection by sonic/ultrasonic testing concrete
- All accessible draped web, longitudinal top deck, diaphragm, and transverse tendons were tested

◆ Verification Testing

- Void verification by drilled holes identified by sonic testing
- Boroscope used to find limits of void



US-54 VIADUCT, WICHITA, KANSAS
NDT & DT INSPECTION
KDOT PROJECT No. : 54-87 KA-1647-01




PREPARED FOR
PB Americas, Inc.
April, 2013




Site Investigation



Site Investigation



Site Investigation



Site Investigation




Site Investigation




Video Borescope Inspection of Ducts

Site Investigation




Inspection Findings

Web Post-tensioned Ducts




Diaphragm Post-tensioned Ducts



Inspection Findings



Inspection Findings



Presentation Outline

- ◆ Introduction
- ◆ Background
- ◆ Site Investigation
- ◆ **Bridge Repair Plans & Repairs**
 - Clean Bridge & Install Bird Screens
 - Epoxy Resin Crack Repair
 - Blister Pour-backs/Anchorage Repair
 - Duct Grouting Operations
 - NDT Grout Verification
 - Test Lead Wire Installation
- ◆ Conclusions



Presentation Outline

- ◆ Introduction
- ◆ Background
- ◆ Site Investigation
- ◆ Bridge Repair Plans & Repairs
 - Clean Bridge & Install Bird Screens
 - Epoxy Resin Crack Repair
 - Blister Pour-backs/Anchorage Repair
 - Duct Grouting Operations
 - NDT Grout Verification
 - Test Lead Wire Installation
- ◆ Conclusions



Bridge Interior





ELEVATION OF HINGE FOR BIRD SCREEN REPAIRS

Adjust spacing of anchor bolts as needed to avoid conflict with existing reinforcement. Contractor shall check for conflicts in the field prior to fabrication.

Bird Screens



Bridge Interior



Presentation Outline

- ◆ **Introduction**
- ◆ **Background**
- ◆ **Site Investigation**
- ◆ **Bridge Repair Plans & Repairs**
 - Clean Bridge & Install Bird Screens
 - **Epoxy Resin Crack Repair**
 - Blister Pour-backs/Anchorage Repair
 - Duct Grouting Operations
 - NDT Grout Verification
 - Test Lead Wire Installation
- ◆ **Conclusions**

Concrete Cracks



Concrete Crack Repair



EPOXY RESIN CRACK REPAIR: Pressure inject epoxy grout into the cracks on the Blisters and Webs in accordance with the manufacturer's specifications and as directed by the Engineer. Repair the cracks that are 0.02" wide or larger. Work shall be performed by individuals qualified to work with this form of rehabilitation. Pay limits for this bid item are estimated crack lengths. Perform work and supply materials and equipment in accordance with KDOT specifications (Section 730). All work and materials required shall be included in the bid item "Bridge Repair", Lump Sum.

Presentation Outline

- ◆ Introduction
- ◆ Background
- ◆ Site Investigation
- ◆ Bridge Repair Plans & Repairs
 - Clean Bridge & Install Bird Screens
 - Epoxy Resin Crack Repair
 - Blister Pour-backs/Anchorage Repair
 - Duct Grouting Operations
 - NDT Grout Verification
 - Test Lead Wire Installation
- ◆ Conclusions

Blister / Tendon Anchorages





NO POUR-BACK
(Type 1)
(Anchor Only)



PARTIAL POUR-BACK
(Type 2)




FULL POUR-BACK
(Type 3)

EXISTING POUR-BACK CLASSIFICATION

EASTBOUND TABLE OF BLISTER POUR-BACKS				
UNIT NO.	SPAN NO.	STR.	NUM. OF BLISTERS	TYPE OF ANCHOR
1	1	EB	12	Partial
1	2	EB	24	Partial
1	3	EB	18	Partial
2	4	EB	8	Full
2	5	EB	16	Partial
3	6	EB	12	Anchor Only
3	7	EB	24	Anchor Only
3	8	EB	16	Anchor Only
4	9	EB	12	Anchor Only
4	10	EB	20	Anchor Only
4	11	EB	8	Anchor Only
5	12	EB	No Blisters	-
5	13	EB	4	Partial
5	14	EB	4	Partial
6	15	EB	No Blisters	-
6	16	EB	4	Full
6	17	EB	4	Full & Partial
7	18	EB	No Blisters	-
7	19	EB	4	Partial
7	20	EB	4	Partial
7	21	EB	No Blisters	-

WESTBOUND TABLE OF BLISTER POUR-BACKS				
UNIT NO.	SPAN NO.	STR.	NUM. OF BLISTERS	TYPE OF ANCHOR
1	1	WB	12	Anchor Only
1	2	WB	24	Anchor Only
1	3	WB	18	Anchor & Partial
2	4	WB	8	Anchor Only
2	5	WB	16	Anchor Only
2	6	WB	16	Anchor Only
3	7	WB	12	Anchor Only
3	8	WB	16	Partial
4	9	WB	12	Anchor Only
4	10	WB	20	Partial
4	11	WB	8	Partial
5	12	WB	No Blisters	-
5	13	WB	4	Partial
5	14	WB	4	Partial
6	15	WB	No Blisters	-
6	16	WB	4	Partial
6	17	WB	4	Partial
7	18	WB	No Blisters	-
7	19	WB	4	Anchor Only
7	20	WB	4	Anchor Only
7	21	WB	No Blisters	-



POUR-BACK REPAIR DETAIL

Blister Repair



Blister Repair



Blister Repair



Blister Repair





Presentation Outline

- ◆ **Introduction**
- ◆ **Background**
- ◆ **Site Investigation**
- ◆ **Bridge Repair Plans & Repairs**
 - Clean Bridge & Install Bird Screens
 - Epoxy Resin Crack Repair
 - Blister Pour-backs/Anchorage Repair
 - **Duct Grouting Operations**
 - NDT Grout Verification
 - Test Lead Wire Installation
- ◆ **Conclusions**

Grouting Operations

Kellogg Bridge, Wichita, Kansas Unit 1 Eastbound



Grouting Operations



Grouting Operations



Grouting Operations




Presentation Outline

- ◆ **Introduction**
- ◆ **Background**
- ◆ **Site Investigation**
- ◆ **Bridge Repair Plans & Repairs**
 - Clean Bridge & Install Bird Screens
 - Epoxy Resin Crack Repair
 - Blister Pour-backs/Anchorage Repair
 - Duct Grouting Operations
 - **NDT Grout Verification**
 - Test Lead Wire Installation
- ◆ **Conclusions**

NDT Verification





Void Found







Re-grouted 8/20/2014
by vacuum grouting

Presentation Outline

- ◆ **Introduction**
- ◆ **Background**
- ◆ **Site Investigation**
- ◆ **Bridge Repair Plans & Repairs**
 - Clean Bridge & Install Bird Screens
 - Epoxy Resin Crack Repair
 - Blister Pour-backs/Anchorage Repair
 - Duct Grouting Operations
 - NDT Grout Verification
 - **Test Lead Wire Installation**
- ◆ **Conclusions**



* The listed tendons contain Soft Grout and will be monitored for potential corrosion as shown on this sheet. See elevation view for location of test lead wires.

Testing per ASTM C876

*** TEST LEAD WIRE LOCATIONS**

UNIT NO.	SPAN NO.	DIR.	CELL NO.	WEB NO.	TEND. NO.	QUANTITY EACH
3	6	EB	2	2	W8	2
3	8	EB	2	2	W8	2
4	11	EB	2	2	W9	2
5	14	EB	2	3	W6	2
W-CBD	3	-	-	2	W1	2
W-CBD	3	-	-	2	W3	2
W-CBD	4	-	-	2	W1	2
W-CBD	4	-	-	2	W3	2

WATER FILLED TENDON

UNIT NO.	SPAN NO.	DIR.	CELL NO.	WEB NO.	TEND. NO.	DEFICIENCY
6	16	WB	1	1	W5	Water

This Tendon shall be drained and re-grouted as per project plan notes.

Test Lead Wires



Half-Cell Potential Readings




Figure 1 (Void with water 2011)




Figure 2 (Voids with soft/wet grout in 2010 but dry at STA 110 in 2011)

- More positive than -200 mV: 90% probability of no corrosion
 - Range of -200 and -350 mV: Corrosion is uncertain
 - More negative than -350 mV: 90% probability of corrosion
- (Note: Potentials versus copper copper-sulfate electrode)




Figure 4 (Void with soft/wet grout and/or accumulated water 2011)





Figure 7 (Void with soft/wet grout and/or accumulated water 2011)

Presentation Outline

- ◆ **Introduction**
- ◆ **Background**
- ◆ **Site Investigation**
- ◆ **Bridge Repair Plans & Repairs**
 - Clean Bridge & Install Bird Screens
 - Epoxy Resin Crack Repair
 - Blister Pour-backs/Anchorage Repair
 - Duct Grouting Operations
 - NDT Grout Verification
 - Test Lead Wire Installation
- ◆ **Conclusions**

- ◆ **14 Bird Screens**
- ◆ **1,236 Linear Feet of Crack Repair (>0.020" wide)**
- ◆ **268 Blister Pour-Backs Replaced**
- ◆ **380 Blister Pour-Backs Coated (all in bridge)**
- ◆ **147 Voids Filled (with 142 ft³ grout, approx. 290 bags)**
 - 15% vacuum grouted
 - 1% vacuum assist
 - 84% pressure grouted
- ◆ **119 Tendons Tested by NDT for Verification**
 - 119 tendons tested by sonic/ultrasonic (80% of filled voids)
 - 64 tendons verified by drilled holes (43% of filled voids)
 - 1 voided tendon found, re-grouted on 8/20/2014
- ◆ **18 Test Lead Wires (on 9 tendons)**

SUCCESS !



- ✦ **Ken Hurst & Loren Risch – KDOT State Bridge Engineer**
- ✦ **Mark Hurt – KDOT Sr. Squad Leader**
- ✦ **Calvin Reed – KDOT State Bridge Engineer (current)**
- ✦ **Annette Ratcliff – KDOT Inspector**
- ✦ **Hideki Fields – KDOT Construction Engineer**
- ✦ **Pci Roads – Contractor**
- ✦ **VSL – Subcontractor**
- ✦ **NDT Corporation – Field Investigation**
- ✦ **Rodney Powers & Associates – Field Investigation**
- ✦ **Wildcat Construction – Field Investigation**
- ✦ **University of Kansas – Dr. David Darwin**
- ✦ **PB Staff**
 - **Teddy Theryo – Technical Director**
 - **Rick Earley – ASBI Certified**

